





NOTES:
 RYTEC CORP. DOES NOT GUARANTEE A FROST FREE DOOR.
 WITH THE HEATED BLOWER SYSTEM HOWEVER, THE AMOUNT OF FROST IS GREATLY
 REDUCED AND THE DEFROST RANGE IS EXPANDED TO APPROXIMATELY 16 FEET.
 DEPENDING ON SITE CONDITIONS AND RELATIVE HUMIDITY, IT IS POSSIBLE FOR FROST
 TO BUILD UP ON THE LOWER PORTION OF THE DOOR PANEL.
 DOOR MUST BE MOUNTED TO THE COLD SIDE OF THE OPENING.
 CONTROL PANEL MUST BE MOUNTED TO THE WARM SIDE OF THE OPENING.

DRAWING NOT TO SCALE, ALL DIMENSIONS IN INCHES										
DOOR NO.	A	B	C1	C2	D	E	F	J	K	M
-	-	-	18	18	20	-	-	-	-	-

ELECTRICAL OPTIONS

- ☐ 460v - 3ph
☐ 230v/208v - 3ph
☐ 575v - 3ph
 (INCLUDES NEMA 4
 METAL ENCLOSURE WITH
 575/460 TRANSFORMER)

STANDARD FEATURES

1. HEATED BLOWER MOUNTED UNDER HEAD
2. STEEL NEMA 4 CONTROL PANEL ENCLOSURE WITH
FUSED ROTARY DISCONNECT FOR TEC LIGHTS.
3. LH MOTOR ASSEMBLY ONLY
4. 45 AMP SERVICE REQUIRED IF "A" < 93"
60 AMP SERVICE REQUIRED IF "A" >= 93"
5. ONLY FLAT HOOD AVAILABLE
6. TURN ARMS W/SEALS.
7. INSULATED SIDE PANELS WITH THERMAL BREAK.
8. 1,2 & 5,6 INTEGRAL PANELS WITH 1&6 INSULATED.
9. 2,3,4,5 PANELS 3/8" TRANSPARENT PVC

STANDARD OPTIONS

- ☐ HEAD PRE-WIRED TO RIGHT SIDE (LEFT STANDARD)
☐ SINGLE SOURCE TRANSFORMER
☐ MOTOR HEATER
☐ SELECTOR SWITCH ON CONTROL BOX
 FUNCTION: _____

ACTIVATION

- ☐ — PUSHBUTTON
☐ — PULL CORDS
☐ — MOTION DETECTOR
☐ — PRESENCE DET.
☐ — MOTION/PRESENCE
☐ DUAL LOOP CONTROLLER
☐ RADIO CONTROL RCVR
 (INCLUDE MIN 2 XMIT)
 — 1 BTN TRANSMITTER
 — 2 BTN TRANSMITTER
 — 4 BTN TRANSMITTER

OPTION NOTES

NOTES:

PLEASE SPECIFY VOLTAGE

RYTEC CORPORATION

ONE CEDAR PARKWAY, JACKSON, WI 53037-0403

APPROVAL DRAWING

FAST FOLD® FREEZER W/ HEATED BLOWER -
COLD SIDE MOUNT

CUSTOMER:

LOCATION:

DATE:

REV.: —

DRAWING NO.: 401014-01T

APPROVAL SIGNATURE

FABRICATION CAN PROCEED ACCORDING TO THE
SPECIFICATION SHOWN EXCEPT AS NOTED

APPROVED BY:

PRINT NAME: _____

SIGNATURE: _____

DATE: _____

FREEZER COOLER

